



1 Platform construction
1 Platform 1/2"-1'

- BUILT WITH 2X4 WOOD.
- COVERED WITH $\frac{5}{8}$ PLYWOOD.
- TOTAL OF 8 PLATFORMS NEED TO BE MADE.
- FASTENED WITH DRYWALL SCREWS

3 Top & Side View of Final Assembly
1 Platform 1/2"-1'

- ADD DYKES 153 HOUSING MOLDING
- FASTEN ALL PLATFORMS WITH DRY WALL SCREWS

2 Outer Leg Construction
1 Legs 1/2"-1'

- BUILT WITH 2X4 WOOD.
- FASTENED WITH DRYWALL SCREWS

NYC COLLEGE OF TECHNOLOGY	
ENT4410-Technical Direction	
Ninety Platforms	PLATE NO
PLATE # 1	1
SCALE:1/2"-1'	
DATE:2/27/2021	
DRAFTER: HENRY CRUZ	OF: 1